



- NOTES:**
1. Joints sealed with Consenal CS101 Butyl Mastic
 2. Concrete: 5000 psi @ 28 days, 5% - 9% air entrainment with 5 lbs / cu. yd of fiber mesh
 3. Equipped with Kor n Seal seals 4'-0" or Equivalent
 4. Design loading H-20 / ASTM C857
 5. Min. 1" concrete cover over reinforcement
 6. Tank to conform with ASTM C1227
 7. Steel reinforcement: #4 rebar horizontally 12" o.c. and #5 rebar vertically 12" o.c.
- A.S.T.M. A496-A615 Grade 60-60 ksi